

2024 Road Overlay Project



Addendum #1

Issue Date: March 20, 2024
Bids Due: March 25, 2024
Time: 1:00 PM
Location: Civic Center
325 E. Aspen Ave.
Fruita, CO 81521

The items contained in this Addendum are hereby issued to answer questions, to revise drawings to correct drawing discrepancies and to issue a new bid schedule reflecting the changes.

This Addendum shall include the following enclosed items:

- A. Addendum 1 bid schedule
- B. Revised plan set
- C. Answers to questions

Drawing Change

On sheet O6 there was discrepancy regarding the type of mill requested by the city. The city desires a full-width, 1-1/2" deep mill on Fremont St.

Question/Answer Section

Q: Does the overlay on S. Peach St. include the bike parking stalls and does the city want to contractor to repaint parking stalls, cross-hatching, etc.?

A: No, the paving will stop short of the bike stalls. The city will perform all striping on S. Peach St.

Q: There appears to be two sheets labeled O3. Please clarify.

A: The city made an error labeling the sheets. Sheet O3 should show Peach St. and new sheet O4 shows Vermont Ln.

Q: The scale bar on the Vermont Ln. sheet appears not to match the dimensions on the plan. Please clarify.

A: The sheet was mislabeled. The scale should read 1"=60'.

Q: Should there be a separate bid item for asphalt leveling course?

A: No, the quantity of asphalt required for a leveling course should be included in bid item 10, Hot Mix Asphalt.

Q: There is a discrepancy in the type of mill requested for N. Fremont St. Does the city desire an edge mill or a full-width mill?

A: The city desires a full-width mill on N. Fremont St.

The Contractor shall acknowledge receipt of this, and any future Addenda on the Bid Schedule to be considered a responsive bid. This Addendum **does not** change the deadline to submit a bid.

**City of Fruita
Addendum 1 Bid Schedule
2024 Road Overlay Project**

<u>No.</u>	<u>Item</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Extension</u>
1	Mobilization	LS	1		
2	Traffic Control	LS	1		
3	Material Testing	LS	1		
4	Stormwater Management	LS	1		
5	Pre/Post Construction Survey	LS	1		
6	Protect Survey Monument	Each	1		
7	Adjust Water Valve to Finished Grade	Each	16		
8	Adjust Manhole Lids to Finished Grade	Each	22		
9	Asphalt Milling/Disposal	SY	12500		
10	Hot Mix Asphalt	Ton	2550		
11	4"-Wide Solid White Striping	LF	2400		
12	4"-Wide Solid Yellow Striping	LF	6000		
13	White Thermoplastic Stop/Crosswalk Bars	SF	166		
Base Bid:					

Company Name: _____

By: _____

Signature: _____

Date: _____

Addendum 1 acknowledgment: _____