



Addendum #4

Issue Date: May 9th, 2024
Bids Due: May 10th, 2024
Time: 1:30 PM
Location: Civic Center
325 E. Aspen Ave.
Fruita, CO 81521

The items contained in this Addendum are hereby issued to answer questions asked prior to the release of this addendum, to revise existing bid items and quantities, and to issue a new bid schedule. This addendum does not change the bid date for the project.

This Addendum shall include the following enclosed items:

- A. Addendum 4 Bid Schedule
- B. Revised Bid Item Quantity: Curb Ramp Quantity
- C. Revised Bid Item 33 Structure Type: Storm Ceptor changed to CDS hydrodynamic separator

Question/Answer Section

Q1:-The bid schedule shows a total of 6 EA Curb Ramps (bid items 22-24), but the plans show a total of 7; 3 EA at Iron Drive, 3 EA at J Road, and 1 EA at J.2 Road.

A: There are a total of 7 Curb Rams being installed for this project. Three at Iron Drive, Three at J Road, and one at J.2 Road as shown on the plans. We will adjust the bid schedule appropriately.

Q2: Will the contractor be responsible for replacing the Aliquot Survey Markers located in 19 Road and in J Road (5 total)?

A: Contractor will only be responsible if there is documented movement of over .10' due to construction, or at the discretion of the Contractor's surveyor. If any Aliquot survey markers do experience excess movement during any phase of construction it will be the sole responsibility of the contractor to replace/reset that monument to the satisfaction of the City Project Manager with no additional payment from the City.

Q3: There is a note in the Ute Water drawings stating that Ute Water will provide survey for the water line. Will Ute Water be providing their own construction staking and as built survey?

A: In order to provide continuity between the different parts of the job the Contractor will provide all surveying for the job, including staking and as built information & drawings.

End of Question/Answer Section

Revised Bid Item Description Section

Item 33 CDS hydrodynamic separator (Structure Type Revision)

This pay item includes furnishing all equipment, materials, and labor necessary to provide and install an “CDS hydrodynamic separator” or approved equivalent as shown on the construction drawings including excavation, excavation bracing, backfill and compaction. Payment for this item will be based on unit prices quoted for each separator.

Items, 22, 23 & 24 Curb Ramp Quantities (Quantity Revision)

Note change to the curb ramp quantities for Type 1, Type 2 & Type 3 in the updated bid document.

End of Revised Bid Item Description Section

End of Addendum #4 - Final Addendum

City of Fruita
Bid Schedule
19 Road Improvement Project - Addendum 4
Project No. 130-750-77-4730

No.	Item Description	Quantity	Unit	Unit Cost	Extension
1	Mobilization	1.0	LS		
2	Clear and Grub	5.5	AC		
3	Construction Surveying	1.0	LS		
4	Material Testing	1.0	LS		
5	Stormwater Management	1.0	LS		
6	Traffic Control	1.0	LS		
7	Flashing Stop Sign	4.0	EA		
8	Variable Message Board	6.0	Days		
9	Reset mail box	17.0	EA		
10	Small Tree Removal (12-Inch Dia. and less)	1.0	LS		
11	Sign (Stop/Speed limit/Etc.)	17.0	EA		
12	Remove Fence	4,100.0	LF		
13	Concrete Curb Gutter & Sidewalk Removal	20.0	LF		
14	Concrete Ditch Removal	700.0	LF		
15	Remove/Plug existing ditch culvert	100.0	LF		
16	Remove/reset Irrigation Pump	2.0	EA		
17	Embankment/Fill	13,000.0	CY		
18	Excavation	13,000.0	CY		
19	Class 6 Aggregate Base Course	17,000.0	TON		
20	Asphalt Milling/Disposal	14,000.0	SY		
21	Hot Mix Asphalt	9,275.0	Ton		
22	Curb Ramp Type 1	1.0	EA		
23	Curb Ramp Type 2	1.0	EA		
24	Curb Ramp Type 3	5.0	EA		
25	4"-Wide Solid White Striping	15,000.0	LF		
26	4"-Wide Solid Yellow Striping	14,000.0	LF		
27	Thermoplastic Crosswalk/Stop Bar Markings	4,785.0	SF		
28	Connect to existing manhole	1.0	EA		
29	4-ft Manhole	15.0	EA		
30	12-inch SDR-35	2,769.7	LF		
31	15-inch SDR-35	1,820.7	LF		
32	4-inch Service Line	1.0	EA		
33	CDS hydrodynamic separator	2.0	EA		
34	60-inch Storm Manhole	12.0	EA		
35	72-inch Storm Manhole	5.0	EA		
36	24"x24" Catch Basin	9.0	EA		
37	12" CMP Driveway Culvert	500.0	LF		
38	15-inch HDPE	544.5	LF		

City of Fruita
Bid Schedule
19 Road Improvement Project - Addendum 4
Project No. 130-750-77-4730

No.	Item Description	Quantity	Unit	Unit Cost	Extension
39	18-inch HDPE	95.0	LF		
40	24-inch HDPE	2,663.1	LF		
41	30-inch HDPE	2,044.9	LF		
42	48-inch RCP	111.3	LF		
43	12" PVC	1,696.4	LF		
44	18" PVC	66.4	LF		
45	24" PVC	501.8	LF		
46	18" RCP	132.6	LF		
47	24" RCP	474.2	LF		
48	Irrigation Box 1A	1.0	EA		
49	Irrigation Box 2A	1.0	EA		
50	Irrigation Box 3A	1.0	EA		
51	Irrigation Tee 1B	1.0	LS		
52	Irrigation Tee 2B	1.0	LS		
53	Irrigation MH 1C	1.0	LS		
54	Irrigation MH 2C	1.0	LS		
55	12" Gate Valve	1.0	EA		
56	GVIC Removal of Structure	1.0	EA		
57	GVIC Structural Excavation	1,175.0	CY		
58	GVIC Structural Backfill (Class 1)	526.0	CY		
59	GVIC Aggregate Base Course (Class 3)	250.0	CY		
60	Concrete Class D (Bridge)	194.0	CY		
61	Structural Concrete Coating	250.0	SF		
62	Reinforcing Steel	28,300.0	LB		
63	8-inch PVC C-900	1,250.0	LF		
64	2-inch Gate Valve	1.0	EA		
65	Air Release/Air Vacuum	2.0	EA		
66	3/4-inch Service Near	3.0	EA		
67	3/4-inch Service Far	3.0	EA		
68	Fire Hydrant Assembly	1.0	EA		
69	Export Unsuitable Backfill Material	9,700.0	CY		
70	Structural Backfill Material	20,000.0	TON		
71	Trench Stabilization Rock	7,200.0	TON		
72	Reconstruct Existing Driveway	25.0	EA		
73	Seeding	6.0	AC		
74	Force Account	1.0	LS	\$500,000.00	\$500,000.00
75	Large Tree Removal	25.0	EA		
76	8" SDR-35	51.0	LF		

**City of Fruita
 Bid Schedule
 19 Road Improvement Project - Addendum 4
 Project No. 130-750-77-4730**

No.	Item Description	Quantity	Unit	Unit Cost	Extension
77	Trail Asphalt	725.0	TON		
78	Highway Intersection Improvements	1.0	LS		
79	Irrigation MH 1B	1.0	EA		
80	36" CMP Culvert Extension	30.0	LF		

Total Base Bid Amount _____

Company Name: _____

By: _____

Signature: _____

Date: _____

Addendum 1 Acknowledgment: _____

Addendum 2 Acknowledgment: _____

Addendum 3 Acknowledgment: _____

Addendum 4 Acknowledgment: _____